

SCHEDULE OF OPENINGS		
DOOR	MD	2.00X2.10
	D	0.90X2.10
	D1	0.75X2.10
WINDOW	W	1.20X1.20
VENTILATOR	V	0.60X0.60

N

AE

Asst. Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore - 92

Scanned by TapScanner



CENTERLINE DETAILS

COLUMN DETAILS

SHAPE OF COLUMNS				
REIN-FORCEMENT	MAIN	10-20ϕ	8-16ϕ	4-12ϕ
	TIES	T8@200C/C	T8@200C/C	T8@200C/C
SIZE OF COLUMNS		450 X 600	230 X 450	230 X 230
LEVEL	TO	TERRACE FLOOR	TERRACE FLOOR	TERRACE FLOOR
	FROM	FOOTING	FOOTING	FOOTING
GRADE OF CONCRETE		M25	M25	M25
DESIGNATION		C1	C2	C3
SHAPE OF TIES				



FOOTING DETAILS

FOOTING NUMBERS	NO. OF FOOTING	FOOTING TYPE	FOOTING DIMENSION			FOOTING REINFORCEMENT	
			L	B	D	BOTTOM	
						ALONG B	ALONG L
F1	6	PAD	3.10	2.90	0.50	12ϕ@125C/C	12ϕ@125C/C
F2	4	PAD	2.30	2.10	0.40	10ϕ@125C/C	10ϕ@125C/C
F3	4	PAD	2.10	1.90	0.35	10ϕ@150C/C	10ϕ@150C/C
F4	3	PAD	1.20	1.20	0.30	10ϕ@150C/C	10ϕ@150C/C

Asst. Executive Engineer
Project Division

TITLE

COLUMN & FOOTING DETAILS

NOTES AND SPECIFICATIONS

1. ALL DIMENSIONS ARE IN INCHES AND FEET FOLLOW THE WRITTEN DIMENSIONS AND DO NOT SCALE THE DRAWING.
2. READ THE DRAWING ALONG WITH RELEVANT ARCHITECTURAL DRAWING AND CO-REALATE THE DETAILS. ANY DISCREPANCY IN THE SAME MAY BE BROUGHT TO THE NOTICE BEFORE COMMENCEMENT OF WORK.
3. THE CEMENT STRENGTH SHOULD BE ASSESED BEFORE CASTING THE QUALITY STRENGTH AND OTHER STANDARDS SHOULD CONFORM TO THE SPECIFICATION IN IS: 269 & IS: 8112 AS PER THE REVELANT AND APPLICABLE STANDARDS.
4. STEEL TO BE USED IN REINFORCEMENT SHOULD BE
   a) TEPED QUALITY HIGH YIELD STRENGTH DEFORMED BARS CONFORMED CONFIRMED AS TO WHERE STANDARDS SHOULD STRICTLY CONFORM TO THE SPECIFICATION IN IS: 1139 & IS:1786-1985.(THE PROOF STRESS OF WHICH SHOULD BE 550N/SQ.MM)
   ALL BARS ABOVE 8M DIA SHOULD BE HYSD BARS.
5. CLEAR COVER TO THE MAIN REINFORCEMENT SHOULD BE:
   25MM FOR BEAMS
   15MM FOR SLABS
   50MM FOR FOOTINGS
   40MM FOR COLUMNS
   35MM FOR GRADE BEAMS
6. THE SBC CONSIDERED FOR THE DESIGN IS 180KN/SQM ANY CHANGES IN THE EXECUTION.
7. THE BUILDING IS DESIGN FOR GROUND + 2 FLOORS ONLY.
8. GRADE OF CONCRETE M25 FOR ALL RCC ITEMS.

PROJECT NAME

ARCHITECT

STRUCTURAL CONSULTANT

Struct-Technology
Architectural Structural Consultants And Contractors
#70, THIRD FLOOR GALAXY MALL BESIDE WOMEN'S COLLEGE
J C NAGAR HUBLI contact.structechnology@gmail.com
+91-8892154978,+91-8310830626,+91-9845887143

DATE	DWG NO	DRN BY	CKD BY
	ST/HB/STR-01	ZAIBA	PUNEET

Scanned by TapScanner



SLAB BEAM FORM WORK

SLAB BEAM DETAILS

BEAM NUMBERS	BREADTH	DEPTH	TOP "ST" BARS	TOP "EX" BARS	BOTTOM "ST"BARS	BOTTOM "EX"BARS	STIRRUPS
B1	230	380	2-16#	2-16#	2-16#	2-16#	2L-8#@150C/C
B2	230	450	2-16#	3-16#	3-16#	2-16#	2L-8#@150C/C
B3	300	750	3-25#	3-25#	3-25#	3-25#	2L-10#@125C/C
B4	230	600	3-16#	2-16#	3-16#	3-16#	2L-8#@150C/C

SLAB DETAILS

SLAB NUMBERS	SLAB DEPTH IN 'MM'	REINFORCEMENT IN SHORTER DIRECTION	REINFORCEMENT IN LONGER DIRECTION	SLAB TYPE
S1	150	10#@150C/C	8#@150C/C	ONE WAY



TYPICAL SECTION OF BEAM

TITLE

SLAB BEAM & SLAB DETAILS

NOTES AND SPECIFICATIONS

1. ALL DIMENSIONS ARE IN INCHES AND FEET FOLLOW THE WRITTEN DIMENSIONS AND DO NOT SCALE THE DRAWING.
2. READ THE DRAWING ALONG WITH RELEVANT ARCHITECTURAL DRAWING AND CO-RELATE THE DETAILS. ANY DISCREPANCY IN THE SAME MAY BE BROUGHT TO THE NOTICE BEFORE COMMENCEMENT OF WORK
3. THE CEMENT STRENGTH SHOULD BE ASSESSED BEFORE CASTING THE QUALITY STRENGTH AND OTHER STANDARDS SHOULD CONFORM TO THE SPECIFICATION IN IS: 269 & IS: 8112 AS PER THE RELEVANT AND APPLICABLE STANDARDS
4. STEEL TO BE USED IN REINFORCEMENT SHOULD BE
   a) FE500S QUALITY HIGH YIELD STRENGTH DEFORMED BARS (EMERGENT DENOTED AS 'S') WHOSE STANDARDS SHOULD STRICTLY CONFORM TO THE SPECIFICATION IN IS 1139 & IS:1786-1985(THE PROOF STRESS OF WHICH SHOULD BE 500N/SQMM)
   ALL BARS ABOVE DIA DIA SHOULD BE HYSD BARS.
5. CLEAR COVER TO THE MAIN REINFORCEMENT SHOULD BE:
   25MM FOR BEAMS
   15MM FOR SLABS
   50MM FOR FOOTINGS
   40MM FOR COLUMNS
   25MM FOR GRADE BEAMS
6. THE SBC CONSIDERED FOR THE DESIGN IS 150KN/SQM ANY CHANGES IN THE EXECUTION.
7. THE BUILDING IS DESIGN FOR GROUND + 2 FLOORS ONLY.
8. GRADE OF CONCRETE M25 FOR ALL RCC ITEMS.

PROJECT NAME

ARCHITECT

STRUCTURAL CONSULTANT

Struct-Technology
Architectural Structural Consultants And Contractors
#70,THIRD FLOOR GALAXY MALL,BESIDE WOMEN'S COLLEGE
J C NAGAR HUBLI.contact.structechnology@gmail.com
+91-8892154978,+91-8310030626,+91-9845887143

DATE	DWG NO	DRN BY	CKD BY
	ST/HB/STR-01	ZAIBA	PUNEET

Asst. Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore - 92

Scanned by TapScanner



PLINTH BEAM FORM WORK

PLINTH BEAM DETAILS

BEAM NUMBERS	BREADTH	DEPTH	TOP "ST" BARS	TOP "EX" BARS	BOTTOM "ST"BARS	BOTTOM "EX"BARS	STIRRUPS
PB1	230	380	2–12#	2–12#	2–12#	2–12#	2L–8#@175C/C
PB2	230	600	2–16#	3–12#	3–16#	3–12#	2L–8#@175C/C
PB3	230	300	2–12#	2–12#	2–12#	2–12#	2L–8#@175C/C
CB	150	150	2–12#	----	2–12#	----	2L–8#@200C/C



TYPICAL SECTION OF BEAM

TITLE

PLINTH BEAM DETAILS

NOTES AND SPECIFICATIONS

1. ALL DIMENSIONS ARE IN INCHES AND FEET FOLLOW THE WRITTEN DIMENSIONS AND DO NOT SCALE THE DRAWING.
2. READ THE DRAWING ALONG WITH RELEVANT ARCHITECTURAL DRAWING AND CO–REALATE THE DETAILS. ANY DESCREPANCY IN THE SAME MAY BE BROUGHT TO THE NOTICE BEFORE COMMENCEMENT OF WORK
3. THE CEMENT STRENGTH SHOULD BE ASSESED BEFORE CASTING THE QUALITY STRENGTH AND OTHER STANDARDS SHOULD CONFORM TO THE SPECIFICATION IN IS: 269 & IS: 8112 AS PER THE REVELANT AND APPLICABLE STANDARDS.
4. STEEL TO BE USED IN REINFORCEMENT SHOULD BE
   a) TESTED QUALITY HIGH YIELD STRENGTH DEFORMED BARS (WHEREVER DENOTED AS Y) WHOSE STANDARDS SHOULD STRICTLY CONFORM TO THE SPECIFICATION IN IS: 1139 & IS:1786–1996.(THE PROOF STRESS OF WHICH SHOULD BE 550N/SQ.MM) ALL BARS ABOVE 6M DIA SHOULD BE HYSD BARS.
5. CLEAR COVER TO THE MAIN REINFORECEMENT SHOULD BE:
   25MM FOR BEAMS
   15MM FOR SLABS
   50MM FOR FOOTINGS
   40MM FOR COLUMNS
   35MM FOR GRADE BEAMS
6. THE SBC CONSIDERED FOR THE DESIGN IS 160KN/SQM ANY CHANGES IN THE EXECUTION.
7. THE BUILDING IS DESIGN FOR GROUND + 2 FLOORS ONLY.
8. GRADE OF CONCRETE M25 FOR ALL RCC ITEAMS.

PROJECT NAME

ARCHITECT

STRUCTURAL CONSULTANT

Struct-Technology
Architectural Structural Consultants And Contractors
#70,THIRD FLOOR GALAXY MALL,BESIDE WOMEN'S COLLEGE
J C NAGAR HUBLI contact,structechnology@gmail.com
+91-8892154978,+91-8310030626,+91-9845887143

DATE	DWG NO	DRN BY	CKD BY
	ST/HB/STR-02	ZAIBA	PUNEET

AE

Asst. Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore - 92

Scanned by TapScanner